



VIA CONSULTING SERVICES, INC.

VIA CONSULTING SERVICES, INC.

MLK - FAIRFAX TO BRENTWOOD WATER MAIN REPLACEMENT

CONTRACT NO.: 215597



PROJECT DESCRIPTION

This \$9.2M project which consists of 4,529 LF of CLDI 20" WM along W. 21st St. between Fairfax St. WTP and Abbott St., and I-95 and Brentwood Blvd., 1,729 LF of CLDI 16" WM along N. Myrtle Ave. between W. 22nd St. and W. 15th St., tie-ins to existing water mains along cross streets and fire hydrant laterals, 2,635 LF of 4" WM for water services along W. 21st St. by open cut, 875 LF HDPE 24" WM under MLK Pkwy by HDD, 205 FL of 30" steel casing by J&B under MLK Pkwy and Norfolk Southern Railroad at N. Myrtle Ave., removal/replacement of existing water services, installation of 25 new water services, abandonment of existing water mains by grout fill, removal/replacement of asphalt/concrete pavement, driveway, sidewalk, curb & gutter, and asphalt milling & resurfacing.

JACKSONVILLE ELECTRIC AUTHORITY

Duval County

DAVID MCDERMET, P.E, PROJECT MANAGER

(904) 665-4626, mcdermet@jea.com