

## HAMILTON ST. BULKHEAD

CONTRACT NO.:  
9894-138



## PROJECT DESCRIPTION

This \$500K project through the City's continuing CEI contract which consisted of performing the final engineering design and construction of the replacement of approximately 86 LF of deficient existing bulkhead on Big Fishweir Creek. This work included removing the deficient existing sheet pile wall and installing a new sheet pile wall and concrete cap within the limited access confines of a residential area and the installation of permanent wall bracing to stabilize another parallel existing bulkhead.

**CITY OF JACKSONVILLE**

Duval County

**FRED SUMTER, PROJECT MANAGER**

(904) 255-8760, fsumter@coj.net